



NOTES:

1. LEAK TEST: 80 PSI, NO BUBBLES 1 MINUTES MINIMUM.
2. HYPOT WITH MATING PLUG, 630 VDC 500 MΩ 0.01 SEC MINIMUM WIRE & HOUSING.
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
4. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).

4	6	AMP #204351-1	CONTACT #22 SOC
3	A/R	PAVE-Seal 150	EPOXY BLACK
2	1	SC3112E10-6P	RCPT 6#20 PINS
1	1	6-4 RA-SS	HOUSING PT4L-SS
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/-0.5
 .X DECIMAL +/- 0.1 .XX DECIMAL +/- 0.02 .XXX DECIMAL +/-0.005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS

2751 Thunderhawk Court
Dayton, Ohio 45414-3445
U.S.A.
(937)890-1100
fax (937)890-5165
www.pavetechnologyco.com

PAVE technology co.

DESCRIPTION *PAVE-Mate II Connectors*
PT4-SS-150-6-20-3112P-SOC

PART NUMBER
0949

REVISION LEVEL
C

PROJECTION