


- NOTES:
1. LEAK TEST: 80 PSI, NO BUBBLES 2 MINUTES MINIMUM.
  2. HYPOT 5000 VDC 500 MEGOHMS 0.01 SEC MINIMUM, ROD TO HOUSING.
  3. ALL TESTS ARE DONE AT ROOM TEMPERATURE.
  4. ALL PARTS MUST PASS ALL TESTS.
  5. MAXIMUM AMPERAGE: 150, MAXIMUM VOLTAGE 10,000 VDC.
  6. NO VOIDS LARGER THAN  $\phi.035$  [.89] ARE ACCEPTABLE.
  7. DIMENSIONS ARE INCHES [millimeters].
  8. USE TWO WRENCHES TORQUED IN OPPOSITE DIRECTIONS TO REDUCE TORQUE TRANSFERRED TO ASSEMBLY.

PAVE STOCK NUMBER: STK 2B

5	1	1104	HOUSING PT12-SS
4	A/R	PAVE-Seal 200HV	EPOXY BLUE
3	1	0049	ROD .375" COPPER HI CURRENT
2	4	BRASS WASH 3/8"	WASHER 3/8" BRASS
1	4	BRASS NUTS 3/8"	NUTS 3/8-16 BRASS HEX
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES  
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/-0.5  
 .X DECIMAL +/- 0.1 .XX DECIMAL +/- 0.02 .XXX DECIMAL +/-0.005  
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



DESCRIPTION PAVE-Seal@ Cable Harnesses  
 PT12-SS-200HV-.38Cu-1.6-1.6

PART NUMBER

1236

REVISION LEVEL

G

PROJECTION

