



**NOTES:**

1. MEGGER TO 500 MEGOHMS MIN AT 630 VOLTS DC .01 SEC
2. HELIUM LEAK TEST - LESS THAT  $1 \times 10^{-8}$  CC/SEC AT 1 ATM  
DIFF. IN DIRECTION SHOWN WITH COPPER GASKET
3. RESISTANCE/CONTINUITY TEST :  
(17X) TW-SH-PR-#18 EX-  
PURPLE- 7.6 OHMS, RED- 5.6 OHMS, SHLD- .16 OHMS
4. THERMAL CYCLE FROM -60°C TO 904. THERMAL CYCLE FROM -60°C FOR 2 CYCLES - 2 HOUR HOLD
5. ID CABLE WITH PAPER LABEL AS SHOWN AND WRAP IN KAPTON TAPE  
(BOTH ENDS OF WIRE) - USE 1/8" MIN LETTERING

3	1	PAVE	PAVESEAL 150	EPOXY
2	2	MDC	191011	COPPER GASKET
1	1	MDC	401005	CF4.62 W/S NIP
ITEM#	QTY	SUP'R	PART NUMBER	DESCRIPTION

**PAVE Technology Co.**

2751 Thunderhawk Court  
Dayton, Ohio 45414-3445  
U.S.A.  
(937)890-1100  
fax (937)890-5165  
www.pavetechnologyco.com

TITLE OR PAVE ORDER CODE  
**CF462-L WIRE HARN**

PART NUMBER  
**1433**

PROJECTION