


NOTES:

1. MEGGER TO 500 MEGOHMS MIN AT 630 VOLTS DC .01 SEC
2. HELIUM LEAK TEST - LESS THAT 1×10^{-8} CC/SEC AT 1 ATM
DIFF. IN DIRECTION SHOWN WITH COPPER GASKET
3. RESISTANCE/CONTINUITY TEST :
(17X) TW-SH-PR-#18 EX-
PURPLE- 7.6 OHMS, RED- 5.6 OHMS, SHLD- .16 OHMS
4. THERMAL CYCLE FROM -60°C TO 904. THERMAL CYCLE FROM -60°C FOR 2 CYCLES - 2 HOUR HOLD
5. ID CABLE WITH PAPER LABEL AS SHOWN AND WRAP IN KAPTON TAPE
(BOTH ENDS OF WIRE) - USE 1/8" MIN LETTERING


3	1	PAVE	PAVESEAL 150	EPOXY
2	2	MDC	191011	COPPER GASKET
1	1	MDC	401005	CF4.62 W/S NIP
ITEM#	QTY	SUP'R	PART NUMBER	DESCRIPTION



PAVE Technology Co.

2751 Thunderhawk Court
Dayton, Ohio 45414-3445
U.S.A.
(937)890-1100
fax (937)890-5165
www.pavetechnologyco.com

TITLE OR PAVE ORDER CODE
CF462-L WIRE HARN

PART NUMBER 1433	PROJECTION 
----------------------------	---

ALL CABLES/SHIELDS/LABELS NOT SHOWN
SEE PAGE 2 FOR COMPLETE CABLE/LABEL ID CONFIGURATION