



LEAK TEST PORT
OR INSTALLATION

NOTES:

1. He LEAK TEST LESS THAN 1 X 10 cc/s AIR EQ. @ 1 ATMOSPHERE.
2. HYPOT TEST 15 kV LESS THAN 5 A LEAKAGE WIRE TO WIRE & HOUSING.
3. MEGGER TEST 500 vdc FOR 20,000 WIRE TO WIRE & HOUSING.

TITLE OR PAVE ORDER CODE	
VS15L-SS-90-2-UL3239#22-60-24	
PART NUMBER	PROJECTION
1500	