



NOTES:

1. a. HE LEAK TEST @1 ATM. $<10^{-6}$ CC/S AIR EQUIVALENT.
b. BUBBLE TEST 80 PSI (GAGE).
2. INSULATION-630 VDC 500 MEGOHMS .01SEC W/MATING PLUGS
3. CONTINUITY TEST W/MATING PLUGS -1.0 OHM MAX
4. 50 OHM IMPEDANCE TEST $\pm 10\%$ W/TDR & RG-141A/U CABLE.
5. HYPOT- 2500 VAC CENTER, SHIELD, & HOUSING .5mA MAX
6. FILLED OUT SPACEHAB ACCEPTANCE DATA PACKAGE REQUIRED.
7. (3) THERMAL CYCLES - BEFORE LEAK & ELECTRICAL TESTING.
-25°C TO 80-25°C WITH 2 HR MIN. SOAK AT EXTREMES.
8. REF- TDR $V_p = .70$

		2751 Thunderhawk Court Dayton, Ohio 45414-3445 U.S.A. (937)890-1100 fax (937)890-5165 www.pavetechnologyco.com
TITLE OR PAVE ORDER CODE		
VS18-SS-200-N (RF COAX CONN)		
PART NUMBER	PROJECTION	
1526		