



VACUUM | ATMOSPHERE

- NOTES:
1. HE LEAK RATE $<10^{-7} \text{ cc/s AE @ 1 ATM}$.
 2. HIPOT TEST: $630 \text{ VDC FOR } .01 \text{ s}$, 500 MEGOHM MIN .
 3. ELECTRICAL CONTINUITY: $<1 \text{ OHM PIN TO SOLDER CUP}$.

		2751 Thunderhawk Court Dayton, Ohio 45414-3445 U.S.A. (937)890-1100 fax (937)890-5165 www.pavetechnologyco.com	
TITLE OR PAVE ORDER CODE			
VS15L-SS-150-7-20-SC-40FB99PN			
PART NUMBER		PROJECTION	
1537			