


NOTES:

1. ALL DIMENSIONS REFERENCE.
2. ELECTRICAL TEST: 630VDC, 500 MEGOHMS, .01sec MIN.
3. HELIUM LEAK TEST: <math><10^{-7}</math> cc/sec AE @ 1 ATM.
4. CONTINUITY TEST CENTER CONDUCTOR AND SHIELD: <math><.5</math> OHM PIN TO WIRE END.

		2751 Thunderhawk Court Dayton, Ohio 45414-3445 U.S.A. (937)890-1100 fax (937)890-5165 www.pavetechnology.co.com	
TITLE OR PAVE ORDER CODE VS18-SS-150-6-RG316-180-40FE6PA			
PART NUMBER 1540		PROJECTION 	