



**NOTES:**

1. LEAK TEST: 500 PSI, THREAD SIDE, 1 MINUTE MIN, NO VISIBLE LEAKS.
2. ELECTRICAL TEST: 630 VDC, 500 MEGOHMS MIN, MATING CONNECTOR TO SOLDER CUPS.
3. CONTINUITY CHECK: RECEPTACLE TO SOLDER CUP, <math><.050</math> OHMS.

		2751 Thunderhawk Court Dayton, Ohio 45414-3445 U.S.A. (937)890-1100 fax (937)890-5165 <a href="http://www.pavetechnologyco.com">www.pavetechnologyco.com</a>	
TITLE OR PAVE ORDER CODE <b>VS18-SS-80-19-20-3112P-SC</b>			
PART NUMBER <b>1547</b>		PROJECTION  	