



NOTES:

1. He LEAK TEST: LESS THEN 1×10^{-7} CC/SEC AT 1 ATM A.E..
2. ELECTRICAL TEST: 630 VDC, 500 MEGOHMS MIN, MATING CONNECTOR TO WIRE LEADS, SEE NOTE 4.
3. CONTINUITY CHECK: RECEPTACLE TO WIRE ENDS $< .050$ OHMS.
4. MATING CONNECTOR IS PLUG W/SOCKET CONTACTS EQUAL TO MS3116F14-18S.



2751 Thunderhawk Court
Dayton, Ohio 45414-3445
U.S.A.
(937)890-1100
fax (937)890-5165
www.pavetechnologyco.com

TITLE OR PAVE ORDER CODE

VS18-SS-150-18-TE20-3112P-120NP

PART NUMBER

1672

PROJECTION

