



NOTES:

1. HE LEAK TEST @1 ATM. $<10^{-8}$ CC/S.
2. HYPOT 630 VDC 500 M Ω 0.01 SEC MINIMUM, WIRE TO WIRE & HOUSING.
3. CONTINUITY TEST W/MATING PLUGS - 1.0 OHM MAX CENTER & SHIELD
4. DC HYPOT TEST @ 5000 VDC FOR 100 M Ω MINIMUM CENTER CONDUCTOR TO SHIELD MHV'S ONLY.
5. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
6. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).
7. THERMAL CYCLE 105° TO -40°C 3 CYCLES 2HR HOLD PRIOR TO TESTING.
8. THESE PARTS ARE CLEANED IN A 1,1,1 TRICHLOROETHYLENE VAPOR THEN PACKAGED IN A LAMINAR FLOW HOOD PROVIDING AN ISO CLASS 5 (CLASS 100) ENVIRONMENT WITHIN THE WORK AREA.

7	4	AMPH# 31-2221	RCPT COAX BNC
6	2	AMPH# 27000	RCPT COAX MHV
5	1	0199	NUT VS22-SS
4	-	-	-
3	1	-224 VITON	O-RING -224 VITON 75
2	A/R	PAVE-Seal 150	EPOXY BLACK
1	1	0189/304SS	HOUSING VS22-304SS
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/-0.5
.X DECIMAL +/- 0.1 .XX DECIMAL +/- 0.02 .XXX DECIMAL +/-0.005
ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS

2751 Thunderhawk Court
Dayton, Ohio 45414-3445
U.S.A.
(937)890-1100
fax (937)890-5165
www.pavetechnologyco.com

PAVE technology co.

DESCRIPTION PAVE-Mate I Connectors
VS22-SS-150-2/1-BNC/MHV-BNC/MHV

PART NUMBER
1699

REVISION LEVEL
J

PROJECTION