



NOTES:

1. LEAK TEST: 80 PSI NO BUBBLES 2.5 MINUTES MIN.
2. HYPOT 630 VDC 500 MEGOHMS .01 SEC MINIMUM, WIRE TO WIRE & HOUSING
3. CONTINUITY TEST: <.5 OHMS PIN TO WIRE END
4. SUPPLIED W/ MATING PLUG SC3126F20-41S, NOT SHOWN.

PAVE technology co.
 2751 Thunderhawk Court
 Dayton, Ohio 45414-3445
 U.S.A.
 (937)890-1100
 fax (937)890-5165
 www.pavetechnologyco.com

TITLE OR PAVE ORDER CODE
PT24-PS-150-41-TE20-3112P-60

PART NUMBER
1751

