



NOTES:

1. HE LEAK TEST @1 ATM. 10^{-8} CC/S AIR EQUIVALENT.
2. HIPOT: 630 VDC 500 MEGOHMS .01SEC W/MATING PLUGS, CENTER CONDUCTOR TO SHIELD TO HOUSING. (SHIELDS ARE FLOATING)
3. CONTINUITY TEST W/MATING PLUGS -1.0 OHM MAX, CENTER CONDUCTOR & SHIELD, END TO END

8	5@14	RG58 A/U	CABLE COAX 50 OHM
7	5	3202-7341-10	JACK CABLE STRAIGHT BNC
6	5	3201-7341-10	PLUG CABLE STRAIGHT BNC
5	1	1014	NUT VS18 SS
4	A/R	SUPER O-LUBE	LUBRICANT O-RING
3	1	-219 VITON 75A	O-RING -219 VITON 75A
2	A/R	PAVE-Seal 150	EPOXY BLACK
1	1	0660	HOUSING VS18 SS
ITEM#	QTY	PART#	DESCRIPTION



TITLE OR PAVE ORDER CODE
VS18-SS-150-5-RG58-6T-6T

PART NUMBER
1774

