



NOTES:

1. HE LEAK TEST @1 ATM. 10^{-5} CC/S.
2. HYPOT 630 VDC 500 MW .01 SEC MINIMUM, WIRE TO WIRE & HOUSING.

6	1	0199	NUT VS22-SS
5	A/R	PAVE-Seal 150	EPOXY BLACK
4	A/R	SUPER O-LUBE	LUBRICANT O-RING SILICONE
3	1	-224 VITON	O-RING -224 VITON 75
2	1	0788	HOUSING VS22-SS IR
1	16@50	TT20	CABLE T/C TYPE T #20 TEFLON FEP
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5
 .X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



TITLE OR PAVE ORDER CODE

VS22-SS-150-16P-TT20-24-24

PART NUMBER

1871

PROJECTION

