



- NOTES:
1. HE LEAK TEST @1 ATM.  $<10^{-7}$  CC/S AIR EQUIVALENT. (AIR EQUIVALENT LEAK RATE/2.73 = ACTUAL He LEAK RATE)
  2. HYPOT 630 VDC 500 MEGOHMS .01 SEC MINIMUM, WIRE TO WIRE & HOUSING.
  3. ALL TESTS ARE DONE AT ROOM TEMPERATURE.
  4. THESE SPECIFICATIONS SUPERSEDE PAVE CATALOG.

7	1	SUPER O-LUBE	LUBRICANT O-RING SILICONE BASED
6	A/R	PAVESEAL 150	EPOXY BLACK
5	1	SC3102A18-12S	RCPT 6 #16 SOCKET
4	1	SC3102A18-12P	RCPT 6 #16 PIN
3	1	-224 VITON	O-RING -224 VITON 75
2	1	0199	NUT VS22-SS
1	1	0189	HOUSING VS22-SS
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES  
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5  
 .X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005  
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS

**PAVE** technology 2751 Thunderhawk Court  
Dayton, Ohio 45414-3445  
U.S.A.  
(937)890-1100  
fax (937)890-5165  
www.pavetechnologyco.com

DESCRIPTION  
**VS22-SS-150-6-16-3102PS(NP)**

PART NUMBER  
**2059**

PROJECTION