



NOTES:
 1. HE LEAK TEST @1 ATM. 10^{-6} CC/S.
 2. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.

5	A/R	SUPER O-LUBE	LUBRICANT O-RING SILICONE
4	1	-215 VITON	O-RING -215 VITON 75
3	A/R	PAVE-Seal 150	EPOXY BLACK
2	1	0183	NUT VS15-SS
1	1	0161	HOUSING VS15L-SS
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/-0.5
 .X DECIMAL +/- 0.1 .XX DECIMAL +/- 0.02 .XXX DECIMAL +/-0.005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



DESCRIPTION
VS15L-SS-150-PLUG

PART NUMBER
2442

PROJECTION

