



NOTES:

1. HE LEAK TEST @1 ATM. 10^{-6} CC/S. WITH O-RING CLEAN W/METHANOL BEFORE INSERTING INTO TEST PORT.
2. 5 KVDC HYPOT TEST WITH 5 mA MAXIMUM LEAKAGE CENTER CONDUCTOR TO LEAK TEST PORT.
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
4. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).

5	1	-016 VITON	O-RING -016 VITON 75
4	A/R	PAVE-Seal 200	EPOXY BLACK
3	1	95F6605	CONTACT #16 SOCKET
2	1	PC18 YELLOW	DABURN 2722/18Y/C OR EQUAL
1	1	0130	HOUSING SPF12-E
ITEM	QTY	PART NUMBER	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES.
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE ± 0.5
 X.X DECIMAL ± 0.1 X.XX DECIMAL ± 0.02 X.XXX DECIMAL ± 0.005
 ANGLES ± 1 DEGREE SURFACE FINISH 128 microinch RMS

	2751 Thunderhawk Court Dayton, OH 45414-3445 U.S.A. tel (937) 890-1100 fax (937) 8905165 www.pavetechnologyco.com	
	DESCRIPTION SPF12-E-200-1-PC18-8-SOC	REVISION LEVEL A
PART NUMBER 2889	PROJECTION	