



NOTES:

1. WIRES ON LOW PRESSURE SIDE TO HAVE .7mm MIN SEPARATION.
2. LEAK TEST, 100% OF UNITS, 80 PSI, NO VISIBLE LEAKS, 1400 PSI, NO VISIBLE LEAKS, 2 MINUTES MIN, QUALIFICATION TEST ONLY.
3. ELECTRICAL TEST: 700 VDC, 500 MEGOHMS MIN WIRE TO WIRE.
4. HELIUM LEAK TEST 15% OF UNITS $<1 \times 10^{-7}$ CC/SEC @ 1 ATM.

Design Library



TITLE OR PAVE ORDER CODE

SP11L-E-200-9-TE24-25CM-50CM

PART NUMBER

1423

PROJECTION

