



**NOTES:**

- 1. LEAK TEST: 80 PSI, NO BUBBLES, 3 MINUTES MIN.
- 2. HYPOT 630 VDC 500 MEGOHMS .01 SEC MINIMUM, WIRE TO WIRE & HOUSING

6	A/R	SUPER-O-LUBE	LUBRICANT, O-RING
5	1	-219 VITON 75A	O-RING, -219, VITON, 75A
4	A/R	PAVE-Seal 150	EPOXY, BLACK
3	3@75	C12-1925 WHITE	WIRE, 12, PVC, TYPE C, WHT
2	1	1014	NUT, VS18, SS
1	1	0107	HOUSING, PT8/VS18, SS
ITEM	QTY	PART#	DESCRIPTION



TITLE OR PAVE ORDER CODE  
**PT8/VS18-SS-150-3-PC12-36-36**

PART NUMBER  
**1717**

