



**NOTES:**

1. LEAK TEST: 900 PSI, NO BUBBLES 10 SECONDS MINIMUM.
2. HYPOT 630 VDC 500 MW 0.01 SEC MINIMUM, CUP TO CUP.
3. CONTINUITY TEST END TO END <0.5 W.
4. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
5. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).

5	A/R	PARKER O-LUBE	LUBRICANT O-RING BARIUM BASED
4	A/R	PAVE-Seal 150	EPOXY BLACK
3	18	AMP #66569	CONTACT #20 SOLDER CUP GOLD PLATED
2	2	-012 VITON	O-RING -012 VITON 75
1	1	1226 SP8L	HOUSING SP8L-E
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES  
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/-0.5  
 .X DECIMAL +/- 0.1 .XX DECIMAL +/- 0.02 .XXX DECIMAL +/-0.005  
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



DESCRIPTION PAVE-Mate® I Connectors

SP8L-E-150-9-22-SC-SC

PART NUMBER

2713

REVISION LEVEL

PROJECTION

