



**NOTES:**

1. HE LEAK RATE <math> < 10^{-7}</math> cc/s AE @1 ATM.
2. HIPOT TEST: 630VDC FOR .01s, 500 MEGOHM MIN.
3. ELECTRICAL CONTINUITY: <math> < 1</math> OHM PIN TO SOLDER CUP.

		2751 Thunderhawk Court Dayton, Ohio 45414-3445 U.S.A. (937)890-1100 fax (937)890-5165 <a href="http://www.pavetechnologyco.com">www.pavetechnologyco.com</a>	
TITLE OR PAVE ORDER CODE <b>VS15L-SS-150-7-20-SC-40FB99PN</b>			
PART NUMBER <b>1537</b>	PROJECTION 		