



NOTES:

- 1. HE LEAK TEST @1 ATM. 10^{-7} CC/S.
- 2. LEAK TEST: 80 PSI, NO BUBBLES 2 MINUTES MIN.
- 3. CHECK OPTICAL CONTINUITY UNDER MICROSCOPE.
- 4. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
- 5. ITEM 3 CUSTOMER SUPPLIED WITH CENTER STRIP.
- 6. HANDLE ITEM 3 CAREFULLY-2" DIA MIN COIL GLASS FIBER BREAKS WHEN BENT SHARPLY.

6	1	0894	NUT VS8-SS
5	A/R	SUPER O-LUBE	LUBRICANT O-RING SILICONE BASED
4	A/R	-112 VITON	O-RING -112 VITON 75A
3	2x60"	3M# PM-6621	FIBER OPTICAL 5u/125 SINGLEMODE PM
2	A/R	PAVE-Seal 150	EPOXY BLACK
1	1	0892	HOUSING VS8-SS
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5
 .X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS

PAVE technology co.
 2751 Thunderhawk Court
 Dayton, Ohio 45414-3445
 U.S.A.
 (937)890-1100
 fax (937)890-5165
 www.pavetechnologyco.com

TITLE OR PAVE ORDER CODE *PAVE-Opti Seal/Fromans.shx; Cable Harnesses*
VS8-SS-150-2-FO(BLUE)-28-28

PART NUMBER **2126** PROJECTION