



NOTES:

1. HE LEAK TEST VACUUM 10×10^{-7} CC/SEC OR LESS.
2. HYPOT 630 VDC 500 MEGOHMS MINIMUM 0.01 SECOND MINIMUM WIRE TO WIRE AND HOUSING.
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
4. ALL PARTS MUST PASS ALL TESTS.
5. WIRE POSITIONING IS APPROXIMATE & VARIABLE.
6. VOIDS LARGER THAN $\phi .035$ [.89] ARE NOT ACCEPTABLE.
7. REF-OPERATING TEMPERATURE -40°C TO 125°C .
8. DIMENSIONS ARE INCHES [millimeters].

ITEM	QTY	PART NUMBER	DESCRIPTION
5	1	0199	NUT VS22-SS
4	1	-224 VITON LT	O-RING -224 VITON 75 LT
3	30	ET24-SLE	CABLE T/C TYPE E#24 TEFLON SLE
2	A/R	PAVE-Seal 150	EPOXY BLACK
1	1	0189	HOUSING VS22-SS

PAVE technology co.

2751 Thunderhawk Court
Dayton, OH 45414-3445
U.S.A.
tel (937) 890-1100
fax (937) 8905165
www.pavetechnologyco.com

DESCRIPTION VS22-SS-150-30P-ETSLE24-300-300	
PART NUMBER 3533	MATERIAL NOTED
REVISION LEVEL -	PROJECTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES.
ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE ± 0.5
X.X DECIMAL ± 0.1 X.XX DECIMAL ± 0.02 X.XXX DECIMAL ± 0.005
ANGLES ± 1 DEGREE SURFACE FINISH 128 microinch RMS