



NOTES:

1. 300 PSIG WORKING PRESSURE

2. QUALIFICATION TESTS:

A THERMALCYCLE TEST @-40°F TO 150 A THERMALCYCLE TEST @-40°F, 1/2hr HOLD @ TEMP, 3 CYCLES

B 1200 PSI NB LEAK TEST FOR 2 min. W/BUBBLE FLUID

C He LEAKAGE TEST NOT EXCEEDING 3x10E-8 cc/sec @ 450 PSI

3. ELECTRICAL TEST 630 VDC @ 500 MEGOHMS

WIRE TO WIRES TO HOUSING

4	1	-011	VITON O-RING
3	A/R	-	PAVESeal 150
2	3 COLORS	UL 1213 or MIL-W-16878D	TE 22 AWG WIRES
1	1	PAVE# 1338	S07-SS HOUSING @1200 PSI
ITEM	QTY	PART NUMBER	DESCRIPTION



2751 Thunderhawk Court
Dayton, Ohio 45414-3445
U.S.A.
(937)890-1100
fax (937)890-5165
www.pavetechnologyco.com

TITLE OR PAVE ORDER CODE

S07-SS 3 WIRE

PART NUMBER

1337

PROJECTION

