



NOTES:

1. LEAK TEST: 80 PSI, 15 MINUTES, 300" SIDE, NO VISIBLE BUBBLES.
2. ELECTRICAL TEST: 630 VDC HYPOT, 500 MEGOHMS MIN, WIRE TO WIRE AND HOUSING.
3. ELECTRICAL TEST: 1000 VAC, WIRE TO WIRE, I N WATER, 5 mA MAX LEAKAGE.
4. CHECK CONTINUITY WIRE TO CONNECTOR, .025 mOHMS MAX.

4	A/R	CPC-19	BLACK URETHANE
3	1	1138	PTN20-PS HOUSING
2	A/R	PAVESEAL 150	EPOXY
1	1	#8 AWG HYPALON CABLE	4 WIRES W/CONNECTOR
ITEM	QTY	ITEM NUMBER	ITEM DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5
 .X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



DESCRIPTION
 PTN20-PS-150-4-H8-300-60w/CON

PART NUMBER

1502

PROJECTION

