



INSTALLATION BORE-
REFERENCE ONLY

NOTES:

1. LEAK TEST: 80 PSI, NO BUBBLES 2 MINUTES MIN.
2. HYPOT 630 VDC 500 MEGOHMS .01 SEC MINIMUM, WIRE TO WIRE.

8	2@35	EE28 19STR ORG	WIRE 28EE MIL-W-16878/5 .014 19/#40
7	1@35	EE28 WHITE	WIRE 28EE MIL-W-16878/5 .014 7/#36
6	1@35	EE28 19STR RED	WIRE 28EE MIL-W-16878/5 .014 19/#40
5	1@35	EE28 19STR BLK	WIRE 28EE MIL-W-16878/5 .014 19/#40
4	1@35	EE28 19STR BLU	WIRE 28EE MIL-W-16878/5 .014 19/#40
3	A/R	PARKER O-LUBE	LUBRICANT O-RING BARIUM
2	1	-010 BUNA	O-RING -010 BUNA 75
1	1	0168	HOUSING SP6-E
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5
X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005
ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



DESCRIPTION
SP6-E-150-6-TEE28-25-9

PART NUMBER

1812

PROJECTION

