


NOTES:
 1. LEAK TEST: 80 PSI, NO BUBBLES 3 MINUTES MIN.
 2. HYPOT 630 VDC 500 MEGOHMS .01 SEC MINIMUM, WIRE TO WIRE & HOUSING.

6	A/R	PARKER O-LUBE	LUBRICANT O-RING BARIUM
5	1	-215 VITON	O-RING -215 VITON 75
4	A/R	PAVE-Seal 150	EPOXY BLACK
3	4@75	PC 12 WHT	WIRE 12PC MILW16878/2 .016 19/#25
2	1	0183	NUT VS15-SS
1	1	1298	HOUSING VS15L/PT8-SS
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5
 X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS

PAVE Technology  2751 Thunderhawk Court
 Dayton, Ohio 45414-3445
 U.S.A.
 (937)890-1100
 fax (937)890-5165
 www.pavetechnologyco.com

TITLE OR PAVE ORDER CODE
VS15L/PT8-SS-150-4-PC12-36-36

PART NUMBER
1856

PROJECTION 