



- NOTES:  
 1. HE LEAK TEST @1 ATM. <math>10^{-6}</math> CC/S.  
 2. HYPOT 630 VDC 500 MW .01 SEC MINIMUM, WIRE TO WIRE.  
 3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.

5	1@37"	TZ2/C#20JTSP	CABLE M27500-20SR2S23
4	3@37"	TZ2/C#24JTSP	CABLE M27500-24SR2S23
3	A/R	SUPER O-LUBE	LUBRICANT O-RING SILICONE
2	1	-016 FLURO	O-RING -016 FLUROSILICONE 75
1	1	0130	HOUSING SPF12-E
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES  
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5  
 .X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005  
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



DESCRIPTION PAVE-Seal/E Cable Harnesses  
 SPF12-E-200-1/3TSP-TZ20/24-18-18

PART NUMBER  
**2100**

