



NOTES:

1. HE LEAK TEST @1 ATM. 10^{-6} CC/S.
2. HYPOT 630 VDC 500 MW .01 SEC MINIMUM, WIRE TO WIRE.
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.

6	3TP@37"	TZ24 WHITE	WIRE 24TZ M22759/44 .006 19/#36
5	2TP@37"	TZ20 WHITE	WIRE 20TZ M22759/44 .006 19/#32
4	1TP@37"	TZ16 WHITE	WIRE 16TZ M22759/44 .007 19/#29
3	A/R	SUPER O-LUBE	LUBRICANT O-RING SILICONE
2	1	-016 FLURO	O-RING -016 FLUROSILICONE 75
1	1	0130	HOUSING SPF12-E
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5
 .X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



DESCRIPTION PAVE-Seal/E Cable Harnesses
 SPF12-E-200-1/2/3TP-TZ16/20/24-18-18

PART NUMBER
2101

