

WIRE LENGTHS	
ITEM	X
3	4
4	9.38
5	9.38
6	8.38

NOTES:

1. LEAK TEST: 80 PSI, NO BUBBLES 30 SECONDS, 100%.
2. HYPOT 1500 VAC 500 MEGOHMS .01 SEC MINIMUM, WIRE TO WIRE & HOUSING.
3. ALL TESTS ARE DONE AT ROOM TEMPERATURE.
4. CONTINUITY FROM WIRE END TO TERMINAL 20 mW MAX.
5. WIRE COLOR LOCATIONS MAY VARY.


8	3	PANDU#DNF18-250	DISCONNECT QUICK FEMALE 1/4"
7	1	PANDUIT#P18-10R	TERMINAL RING #10
6	41.37	TZ18 WHT/ORG	WIRE MIL-W-22759/34 .067 19/#30
5	42.37	TZ18 YEL	WIRE MIL-W-22759/34 .067 19/#30
4	42.37	TZ18 BRN	WIRE MIL-W-22759/34 .067 19/#30
3	36.99	TZ18 GRN	WIRE MIL-W-22759/34 .067 19/#30
2	A/R	PAVE-Seal 80	EPOXY BLACK
1	1	1308-B	HOUSING PT6-B
ITEM	QTY	PART#	DESCRIPTION

PAVE will meet the assembly and test specifications of the customer as documented on this assembly drawing. Any changes must be approved by PAVE.



DESCRIPTION
PT6-B-80-4-TZ18-30-4T

PART NUMBER
2179



ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5
.X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005
ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS