



INSTALLATION/
LEAK TEST PORT

NOTES:

1. LEAK TEST: 400 PSI, NO BUBBLES 1 MINUTE MINIMUM.
2. HYPOT 630 VDC 500 MW 0.01 SEC MINIMUM, WIRE TO WIRE & HOUSING
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
4. WIRE ARRANGEMENT AND POSITIONS MAY VARY.

8	25"	E12 WHITE	WIRE 12E MIL-W-16878/4 .013 19/#25
7	25"	E12 YELLOW	WIRE 12E MIL-W-16878/4 .013 19/#25
6	25"	E12 RED	WIRE 12E MIL-W-16878/4 .013 19/#25
5	25"	E12 GREEN	WIRE 12E MIL-W-16878/4 .013 19/#25
4	A/R	PAVE-Seal 150	EPOXY BLACK
3	1	-908 BUNA	O-RING -908 BUNA 90
2	A/R	PARKER O-LUBE	LUBRICANT O-RING BARIUM-BASED
1	1	2147	HOUSING SO12-SS
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/-0.5
 .X DECIMAL +/- 0.1 .XX DECIMAL +/- 0.02 .XXX DECIMAL +/-0.005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



DESCRIPTION PAVE-Seal® Cable Harnesses
 SO12-SS-150-4-TE12-12-12

PART NUMBER
2365

