



NOTES:

1. HE LEAK TEST @1 ATM. 10^{-8} CC/S.
2. HYPOT 630 VDC 500 MW 0.01 SEC MINIMUM, WIRE TO WIRE TO SHIELDS & HOUSING.
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
4. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE

A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).

5. SHIELDING NEED NOT BE CARRIED THROUGH HOUSING.

9	1@14"	CABLE 3/C #22	CABLE 3/C E22
8	1@14"	CABLE 2/C #22	CABLE 2/C E22
7	1@14"	CABLE 2/C #16	CABLE 2/C E16
6	3@14"	CABLE 4/C #22	CABLE 4/C E22
5	A/R	SUPER-O-LUBE	O-RING LUBRICANT
4	1	-215 VITON	O-RING -215 VITON 75
3	A/R	PAVE-Seal 150	EPOXY BLACK
2	1	0183	NUT VS15-SS
1	1	0161	HOUSING VS15L-SS
ITEM	QTY	PART #	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/-0.5
 .X DECIMAL +/- 0.1 .XX DECIMAL +/- 0.02 .XXX DECIMAL +/-0.005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



DESCRIPTION
 VS15L-SS-150-3/1/1/1-4C/2C/2C/3C-6-6

PART NUMBER

2447

REVISION LEVEL

-

PROJECTION

