



NOTES:

1. LEAK TEST: 110 PSI, NO BUBBLES 4 MINUTES MINIMUM.
2. HYPOT 630 VDC 500 MEGOHMS MINIMUM 0.01 SECOND MINIMUM WIRE TO WIRE AND HOUSING.
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
4. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).
5. REF-OPERATING TEMPERATURE -20°C TO 150°C.

| 4 | 1 | 647160 | CABLE 3 #8 100" |
|------|-----|---------------|------------------|
| 3 | A/R | URETHANE | URETHANE BLACK |
| 2 | A/R | PAVE-Seal 150 | EPOXY BLACK |
| 1 | 1 | 1503 | HOUSING PTN20-PS |
| ITEM | QTY | PART NUMBER | DESCRIPTION |

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES.
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE ±0.5
 X.X DECIMAL ±0.1 X.XX DECIMAL ±0.02 X.XXX DECIMAL ±0.005
 ANGLES ±1 DEGREE SURFACE FINISH 128 microinch RMS

PAVE technology co.
 2751 Thunderhawk Court
 Dayton, OH 45414-3445
 U.S.A.
 tel (937) 890-1100
 fax (937) 8905165
 www.pavetechnologyco.com

DESCRIPTION
PTN20-PS-150-3-H8-18-82

PART NUMBER
2898

REVISION LEVEL
A

PROJECTION