



NOTES:

1. LEAK TEST: 110 PSI, NO BUBBLES 6 MINUTES MINIMUM.
2. HYPOT 630 VDC 500 MEGOHMS MINIMUM 0.01 SECOND MINIMUM WIRE TO WIRE AND HOUSING.
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
4. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).
5. REF-OPERATING TEMPERATURE -20°C TO 150°C.
6. END STRIP MAY BE LONGER IF STRIPPED BY CUSTOMER.

PART #	PART DESCRIPTION	A	ITEM#1	ITEM#1 DESCRIPTION
2899	PTN20-PS-150-1-4#10-43-104	43	647161	CABLE 4 #10 150° TERMINATED
2899-1	PTN20-PS-150-1-4#10-48-99	48	647162	CABLE 4 #10 150° TERMINATED
2899-2	PTN20-PS-150-1-4#10-57-90	57	653797	CABLE 4 #10 150° TERMINATED

4	A/R	URETHANE	URETHANE BLACK
3	A/R	PAVE-Seal 150	EPOXY BLACK
2	1	1503	HOUSING PTN20-PS
1	1	SEE TABLE	SEE TABLE
ITEM	QTY	PART NUMBER	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES.  
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE ±0.5  
 X.X DECIMAL ±0.1 X.XX DECIMAL ±0.02 X.XXX DECIMAL ±0.005  
 ANGLES ±1 DEGREE SURFACE FINISH 128 microinch RMS

	2751 Thunderhawk Court Dayton, OH 45414-3445 U.S.A. tel (937) 890-1100 fax (937) 8905165 www.pavetechnologyco.com	
	DESCRIPTION PTN20-PS-150-1-4#10-*A-150 *SEE TABLE	
PART NUMBER <b>2899</b>	REVISION LEVEL <b>C</b>	PROJECTION 