

- HE LEAK TEST VACUUM 10X10^-7 CC/SEC OR LESS.
- 2. HYPOT 630 VDC 500 MEGOHMS MINIMUM 0.01 SECOND MINIMUM WIRE TO WIRE AND HOUSING.
- ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
- ALL PARTS MUST PASS ALL TESTS.
- WIRE POSITIONING IS APPROXIMATE & VARIABLE.
- WIRES ARE NOT REQUIRED TO BEND SHARPLY AT EPOXY SEAL SURFACE.
- VOIDS LARGER THAN \emptyset .035 [.89] ARE NOT ACCEPTABLE.
- REF-OPERATING TEMPERATURE -20°C TO 125°C, CABLE UL RATED TO 90°C MAXIMUM.
- 9. DIMENSIONS ARE INCHES [millimeters].

			NW40-SS-150-3CABLE-4C18-240-120	
ITEM	QTY	PART NUMBER	DESCRIPTION	tel (937) 890-1100 fax (937) 8905165 www.pavetechnologyco.com
1	1	3583	HOUSING NW40-SS	Dayton, OH 45414-3445 U.S.A.
2	A/R	PAVE-Seal 150	EPOXY BLACK	2751 Thunderhawk Court
3	3	9936K18	CABLE 4/C #18 .028"OD 600VAC GRAY PVC	

3848

NOTED \bigcirc