

NOTES:

- HE LEAK TEST VACUUM 10X10^-9 CC/SEC OR LESS.
- HYPOT 1000 VDC 500 MEGOHMS MINIMUM 0.01 SECOND MINIMUM WIRE TO WIRE AND HOUSING.
- ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
- ALL PARTS MUST PASS ALL TESTS.
- WIRE POSITIONING IS APPROXIMATE & VARIABLE.
- VOIDS LARGER THAN \emptyset 0.035 [.89] ARE NOT ACCEPTABLE.
- REF-OPERATING TEMPERATURE -20°C TO 125°C. DIMENSIONS ARE INCHES [millimeters].

ITEM	QTY	PART NUMBER	DESCRIPTION
1	1	4062	HOUSING NW16-AL
2	A/R	PAVE-Seal 150	EPOXY BLACK
3	4	KAPTON 24 TWST	WIRE KAPTON #24 TWISTED PAIR ACCU-GLASS #112677

VE ledinologij co.

2751 Thunderhawk Court Dayton, OH 45414-3445 U.S.A. tel (937) 890-1100 fax (937) 8905165

NW16-AL-150-4TP-K24-8-8

4033

NOTED \bigcirc