


PT2 WRENCH TIGHT
AT .236 DP
PT2 FINGER TIGHT
AT .162 DP

1200 PSI
LEAK TEST
SEE NOTE 1

ITEM	QTY	DESCRIPTION
1	1	HIGH VOLTAGE COAX CABLE, CUST SUP
2	1	SHIELD FERRULE, PAVE #1154 REV A
3	1	PT2 REV A-SS HOUSING, PAVE #1152 REV A
4	A/R	PAVESEAL 200HV EPOXY
5	1	BIFURCATED PIN CONTACT, PAVE #1153 REV A


NOTES:

1. LEAK TEST: 1200 PSI NITROGEN, THREAD SIDE, NO VISIBLE LEAKS, 3 MINUTES.
2. ELECTRICAL TEST: 10,000 VDC, 20 MICRO AMPS MAX, WIRE TO HOUSING (SHIELD).
1 OHM CONTINUITY MAX, CONDUCTOR TO PIN AND SHIELD TO PT2-SS HOUSING.
3. PIN TO FIT SNUG IN ø.089 3. PIN TO FIT SNUG IN ±.001 HOLE BEYOND FINGER TIGHT DEPTH.



2751 Thunderhawk Court
Dayton, Ohio 45414-3445
U.S.A.
(937)890-1100
fax (937)890-5165
www.pavetechnologyco.com

TITLE OR PAVE ORDER CODE
PT2-SS 10KV COAX ASY.

PART NUMBER 1151	PROJECTION 
----------------------------	---