


4	2	-	10 KV CABLE
3	-	-	PAVESeal 200
2	1	PAVE #0165 REV D	SO16L SS HOUSING
1	3	-	RG316 COAX
ITEM	QTY	PART NUMBER	DESCRIPTION

NOTES:

- HELIUM LEAK TEST THREAD END 1x10-8 cc/s @1 ATMOSPHERE
- ALL DIMENSIONS & TOLERANCES IN INCHES
- 5KVAC HYPOT ALL WIRES & HOUSING
- 5KV MEGGER TEST @ 2000 MEGOHMS BETWEEN CENTER CONDUCTOR, SHIELD,

WIRES & HOUSING

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES  
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5  
 .X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005  
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS


 2751 Thunderhawk Court  
 Dayton, Ohio 45414-3445  
 U.S.A.  
 (937)890-1100  
 fax (937)890-5165  
 www.pavetechnologyco.com

DESCRIPTION

SO16L W/3 COAX & 2 HV CABLES

PART NUMBER

1306

PROJECTION

