


ITEM	QTY	PART NUMBER	DESCRIPTION
1	4	SPACECRAFT #SC3124E16-26P	RECEPTACLE, JAM NUT, 16 SHELL SIZE
2	364'	24 AWG TYPE E TEFLON WIRE	TE24 WIRE, 104 PC'S, 42" OAL
3	A/R	PAVESEAL 150	EPOXY POTTING
4	1	PAVE #1362	VS31-B HOUSING
5	1	PARKER 2-233 V747-75	O-RING, FLUOROCARBON, 75 DUROMETER
6	3	PAVE #1363	VS31-B JAM NUT, (2 NOT SHOWN)
7	4	SPACECRAFT #SC3124E16-26S	RECEPTACLE, JAM NUT, 16 SHELL SIZE
8	4	SPACECRAFT #SC3126F16-26S	PLUG, STRAIGHT, W/STRAIN RELIEF
9	4	SPACECRAFT #SC3126F16-26P	PLUG, STRAIGHT, W/STRAIN RELIEF

- NOTES:
1. ELECTRICAL TEST: 630 VDC, 500 MEGOHMS MIN WIRE TO WIRE AND CONNECTOR TO CONNECTOR AND HOUSING
  2. CHECK CONTINUITY AND PINOUT OF CONNECTORS WITH MATING PLUGS, CONTINUITY LESS THEN 1 OHM.
  3. LEAK TEST, 210 PSI HEX SIDE, 2 MINUTES MIN, NO VISIBLE LEAKS, TO BE DONE BEFORE ADDING CONNECTORS.


 2751 Thunderhawk Court  
 Dayton, Ohio 45414-3445  
 U.S.A.  
 (937)890-1100  
 fax (937)890-5165  
 www.pavetechnologyco.com

TITLE OR PAVE ORDER CODE  
**VS31-B-150 104 WIRE**

PART NUMBER  
**1336**

PROJECTION

