



NOTES:

1. LEAK TEST @ 1000 PSI W/N2. NO BUBBLING PERMITTED.
2. ELECTRICAL TEST IN SALT WATER 630VDC 500MEGOHMS .01S.
3. VS NUT NOT SHOWN.

9	A/R	URETHANE	URETHANE, BLACK 70A
8	A/R	SUPER O-LUBE	O-RING LUBRICANT
7	1	-219 VITON 75A	O-RING
6	1	PAVE 0660	VS18 HOUSING, SS
5	2 @ 11.5'	ALPHA 7622	CABLE, TWISTED SHIELDED PAIR
4	2 @ 11.5'	22AWG TP	PVC TWISTED PAIR, #22
3	1 @ 11.5'	RG179 COAX	CABLE, COAX RG179 75 W
2	2 @ 11.5'	RG174 COAX	CABLE, COAX RG174 50 W
1	A/R	PAVE-Seal 150	EPOXY, BLACK
ITEM#	QTY	PART NUMBER	DESCRIPTION



TITLE OR PAVE ORDER CODE
VS18-SS-150-7-RG174+C-12-120

PART NUMBER

1461

PROJECTION

