



NOTES:

1. LEAK TEST @20 PSI N₂, 330 SEC MIN, NO VISIBLE BUBBLES.
2. HIPOT TEST @630VDC, 500 MEGOHMS, 10 ms MIN, WIRE TO WIRE & HOUSING



TITLE OR PAVE ORDER CODE
ASA11-SS-150-900-TE20-60-60

PART NUMBER
1501

