



NOTES:

1. LEAK TEST: 80 PSI, 6 MINUTES MIN, NO VISIBLE BUBBLES.
2. ELECTRICAL TEST: 630 VDC, 500 MEGOHMS MIN, WIRE TO WIRE & HOUSING.
3. HOUSING DIMENSIONS REFERENCE.

3	A/R	PAVESEAL 150	EPOXY
2	1	1308-SS	HOUSING, PT6-SS W/INT O-R
1	5@122	KT24	WIRE, THERMOCOUPLE, 24AWG
ITEM	QTY	PART #	DESCRIPTION



DESCRIPTION

PT6-SS-150-5P-KT24-84-36

PART NUMBER

1604

PROJECTION



ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5
 .X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS