

## NOTES:

- HE LEAK TEST VACUUM 10X10^-9 CC/SEC OR LESS.
- HYPOT 630 VDC 500 MEGOHMS MINIMUM 0.01 SECOND MINIMUM WIRE TO WIRE AND HOUSING.
- 3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
- ALL PARTS MUST PASS ALL TESTS.
- WIRE POSITIONING IS APPROXIMATE & VARIABLE.
- VOIDS LARGER THAN  $\emptyset$ .035 [.89] ARE NOT ACCEPTABLE.
- REF-OPERATING TEMPERATURE -20 °C TO 125 °C.
- DIMENSIONS ARE INCHES [millimeters].

| ITEM | QTY | PART NUMBER   | DESCRIPTION                |
|------|-----|---------------|----------------------------|
| 1    | 1   | 3583          | HOUSING NW40-SS            |
| 2    | A/R | PAVE-Seal 150 | EPOXY BLACK                |
| 3    | 5   | TT24          | CABLE T/C TYPE T#24 TEFLON |

PAVE ledmology co.

2751 Thunderhawk Court Dayton, OH 45414-3445 U.S.A. tel (937) 890-1100

fax (937) 8905165

NW40-SS-150-5P-TT24-1M-1M

1680

RIAL NOTED

 $\bigcirc$