



**NOTES:**

1. HE LEAK TEST @1 ATM.  $<10^{-7}$  CC/S AIR EQUIVALENT W/ VITON GASKET G-275V  
(AIR EQUIVALENT LEAK RATE/2.73 = ACTUAL He LEAK RATE)
2. HYPOT 630 VDC 500 MEGOHMS .01 SEC MINIMUM, WIRE TO WIRE & HOUSING
3. ASSEMBLY TO SHIP W/ COPPER GASKET.

TITLE OR PAVE ORDER CODE	
CF275-SS-200-52-TE24-12-12	
PART NUMBER	PROJECTION
1711	