



**NOTES:**

1. PRESSURE TEST @ 1500 PSI, NO BUBBLES 10 SEC MIN.
2. HYPOT 630 VDC 500 MEGOHMS .01 SEC MINIMUM, PIN TO PIN & HOUSING.
3. CONTINUITY TEST W/MATING PLUGS <1.0 OHM.
4. MATING PLUGS NOT SUPPLIED ON THIS ASSEMBLY, ORDER SEPARATELY AS SC3106A36-78S & SC3106A36-78P.

7	A/R	SUPER O-LUBE	LUBRICANT O-RING SILICONE
6	1	-231 VITON	O-RING -231 VITON 75
5	A/R	PAVE-Seal 150	EPOXY, BLACK
4	1	SC3102A36-78S	RCPT 12#8 2#16 SOCKETS
3	1	SC3102A36-78P	RCPT 12#8 2#16 PINS
2	1	0102	NUT VS32-SS
1	1	0101	HOUSING VS32-SS [303 STAINLESS]
ITEM	QTY	PART#	DESCRIPTION



TITLE OR PAVE ORDER CODE  
**VS32-SS-150-12/2-8/16-3102SP(NP)**

PART NUMBER  
**1758**

