



**NOTES:**

1. HE LEAK TEST @1 ATM. <math>10^{-7}</math> CC/S.
2. LEAK TEST: 80 PSI, NO BUBBLES 2 MINUTES MIN.
3. CHECK OPTICAL CONTINUITY UNDER MICROSCOPE.
4. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
5. ITEM 3 CUSTOMER SUPPLIED.
6. HANDLE ITEM 3 CAREFULLY-2" DIA MIN COIL GLASS FIBER BREAKS WHEN BENT SHARPLY.

7	1	0894	NUT VS8-SS
6	A/R	SUPER O-LUBE	LUBRICANT O-RING SILICONE BASED
5	A/R	-112 VITON	O-RING -112 VITON 75A
4	4x1	A-STT-30	TUBING .012"ID TEFLON SPAGHETTI
3	2x85"	3M# PM-250	FIBER OPTICAL 1.3u/125 SINGLEMODE PM
2	A/R	PAVE-Seal 150	EPOXY BLACK
1	1	0892	HOUSING VS8-SS
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES  
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5  
 .X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005  
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS

2751 Thunderhawk Court  
 Dayton, Ohio 45414-3445  
 U.S.A.  
 (937)890-1100  
 fax (937)890-5165  
 www.pavetechnologyco.com

**PAVE Technology Co.**

TITLE OR PAVE ORDER CODE [PAVE-Opti SealFromans.shx; Cable Harnesses](#)  
**VS8-SS-150-2-FO(CLEAR)-1-1M**

PART NUMBER **2127** PROJECTION