



NOTES:

1. LEAK TEST: 80 PSI, NO BUBBLES 10 SECONDS MINIMUM.
2. HYPOT 630 VDC 500 MΩ 0.01 SEC MINIMUM, CENTER, SHELL & HOUSING WITH MATING CONNECTORS.
3. CONTINUITY 1.0 Ω MAX CENTER TO CENTER & SHELL TO SHELL.
4. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
5. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).
6. UNIT CONSTRUCTED WITH FLOATING SHIELD.
7. NO TDR TEST OR IMPEDANCE CHECK.

3	1	1625	HOUSING PT16-SS
2	A/R	PAVE-Seal 150	EPOXY BLACK
1	2	AMP #227760-2	RCPT TNC PANEL FEMALE
ITEM	QTY	PART NUMBER	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/-0.5
 .X DECIMAL +/- 0.1 .XX DECIMAL +/- 0.02 .XXX DECIMAL +/-0.005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



DESCRIPTION	PAVE-Mate® I Connectors PT16-SS-150-TNC-TNC	
PART NUMBER	2172	REVISION LEVEL
		A
PROJECTION		