


NOTES:

1. HE LEAK TEST @1 ATM. 10^{-8} CC/S.
2. HYPOT 630 VDC 500 M Ω .01 SEC MINIMUM, WIRE TO WIRE & HOUSING.
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
4. ETCH OR ENGRAVE HEX FLATS AS SHOWN.

6	1	0199	NUT VS22-SS
5	A/R	PAVE-Seal 150	EPOXY
4	A/R	SUPER O-LUBE	LUBRICANT O-RING SILICONE BASED
3	1	-224 VITON	O-RING -224 VITON 75A
2	1	0189	HOUSING VS22-SS
1	25@9.50'	ET24-SLE	CABLE T/C TYPE E#24 TEFLON SLE
ITEM	QTY.	ITEM NUMBER	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/-0.5
 .X DECIMAL +/- 0.1 .XX DECIMAL +/- 0.02 .XXX DECIMAL +/-0.005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS


 2751 Thunderhawk Court
 Dayton, Ohio 45414-3445
 U.S.A.
 (937)890-1100
 fax (937)890-5165
 www.pavetechnologyco.com

DESCRIPTION *PAVE-Seal@ Cable Harnesses*
VS22-SS-150-25P-ET24SLE-60-48

PART NUMBER	REVISION LEVEL
2184	-
PROJECTION	