



- NOTES:  
 1. HE LEAK TEST @1 ATM. <math>10^{-7}</math> CC/S.  
 2. HYPOT 630 VDC 500 MW 0.01 SEC MINIMUM, CENTER CONDUCTOR TO SHIELDING & HOUSING.  
 3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.

6	6@98	RG178	WIRE COAX M17/93 FEP 7 STRAND
5	1	1014	NUT VS18 SS
4	A/R	SUPER O-LUBE	LUBRICANT O-RING
3	1	-219 NITRILE LT	O-RING -219 NITRILE N0304-75
2	A/R	PAVE-Seal 150	EPOXY BLACK
1	1	0660	HOUSING VS18 SS
ITEM#	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES  
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/- .5  
 .X DECIMAL +/- .1 .XX DECIMAL +/- .02 .XXX DECIMAL +/- .005  
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS



DESCRIPTION PAVE-Seal® Cable Harnesses  
 VS18-SS-150-6-RG178-48-48

PART NUMBER  
**2393**

