



NOTES:

1. LEAK TEST: 80 PSI, NO BUBBLES 2 MINUTES MINIMUM.
2. HYPOT 630 VDC 500 MEGAOHMS MINIMUM 0.01 SECOND MINIMUM WIRE TO WIRE AND HOUSING.
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
4. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).

5	A/R	PAVE-Seal 150	EPOXY BLACK
4	A/R	SUPER O-LUBE	LUBRICANT O-RING SILICONE-BASED
3	1	11x1.5MM VITON	O-RING 11mm ID x 1.5mm CS VITON 75
2	1	2670	HOUSING SO8X-AL
1	19	TZ30 WHITE	WIRE 30 TEFZEL M22759/32 7#38
ITEM	QTY	PART NUMBER	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES  
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE #0.5  
 XX DECIMAL ±0.1 XXX DECIMAL ±0.02 XXXX DECIMAL ±0.005  
 ANGLES ±1 DEGREE SURFACE FINISH 128 microinch RMS

	2751 Thundehawk Court Dayton, OH 45414-3445 U.S.A. tel (937) 890-1100 fax (937) 8905165 www.pave-technologyco.com	
	DESCRIPTION <b>SO8X-AL-150-19-TZ30-15-15</b>	REVISION <b>A</b>
PART NUMBER <b>2638</b>	PROJECTION 	